

## SECTION 01010

### SUMMARY OF PROJECT

#### PART 1 - GENERAL

##### 1.01 WORK COVERED BY CONTRACT DOCUMENTS

- A. These Contracts are for the restoration of the lake banks of Gateway Lakes 60, 61, 90, 110, 119, and 121 as specified herein. Restoration shall be accomplished by use of an anchor reinforced vegetation system (ARVS) or other repair cross section as shown on the Drawings. The Work consists of furnishing all labor, all equipment, and materials required for construction, consisting of but not limited to the following:

- i. Providing all surveying and field engineering services to establish vertical and horizontal datum and control. Staking residential lot lines, lake maintenance easement locations, and all other services necessary to complete the work as required by the contract documents.
- ii. All excavation, fill, and compaction required to establish a consistent slope along the lake as shown on the Drawings.
- iii. Installation of an ARVS along the perimeter of the lake as shown on the Drawings.

Note: All material for this Contract shall be furnished and installed by the Contractor. No material or equipment will be provided by the Owner.

##### 1.02 CONTRACTOR'S USE OF PREMISES

- A. The Contractor shall assume full responsibility for the protection and safekeeping of products and materials at the job site. If additional storage or work areas are required, they shall be obtained by the Contractor at no additional cost to the Owner.
- B. Staging areas, access points, parking areas, and locations for jobsite restrooms will be identified to the Contractor. These identified areas will be the only areas available to the Contractor and only these areas shall be used. If the Contractor wishes to use areas outside of these designated locations they shall submit a written request to the GSCDD identifying the alternative areas. This request will be reviewed and either approved or denied in writing.

##### 1.03 PROJECT SEQUENCE AND CONTRACT TIME

- A. The work shall be completed as follows:

- i. The total Contract Time from issuance of the Notice-to-Proceed to substantial completion will be 90 calendar days. An additional 30 days will be provided to reach

final completion. If more than one contract is issued to the same vendor, no additional time shall be supplied to complete the work (the contract time shall remain as stated above).

- ii. Contractor shall coordinate with GSCDD in notifying all residents affected by construction at least 15 days prior to the start of construction
- B. The Contractor shall establish his work sequence based on the use of crews to facilitate completion of construction and testing within the specified Contract Time.
- C. The Contractor shall be limited to working on no more than one thousand linear feet (1000') of shoreline at any given time and must complete restoration of this area prior to proceeding with the restoration of more shoreline. The installation of the ARVS (or other repair material), sod, and #57 stone must be complete in the one thousand foot (1000') section prior to proceeding with the subsequent section of shoreline.

PART 2 – PRODUCTS (NOT USED)

PART 3 – EXECUTION (NOT USED)

END OF SECTION